


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Harper County, Sec 17 Twp. 33 Rge. (E) 7 (W)

Location as "NE/CNW%SW%" or footage from lines NW SE
Lease Owner Pickrell Drilling Company
Lease Name Tysor Well No. 1
Office Address 705 4th National Bank Building, Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed December 22, 1962
Application for plugging filed December 22, 1962
Application for plugging approved December 22, 1962
Plugging commenced December 22, 1962
Plugging completed December 22, 1962
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5012 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	215'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 180'. Set plug. Cemented with
20 sacks cement. Heavy mud to 40'. Set Plug.
Cemented with 10 sacks cement to bottom of
cellar. Plugged rat hole with 2 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

DEC 28 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor PICKRELL DRILLING COMPANY
Address 705 4th National Bank Building, Wichita, Kansas


STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

C. W. SEBITS (employee of owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) C. W. Sebits
705 4th National Bank Building, Wichita, Kansas
(Address)

Subscribed and sworn to before me this 26th day of December, 1962
My commission expires June 21, 1966

Maxine Blackman
Notary Public.



ROTARY DRILLING LOG

COMPANY: PICKRELL DRILLING COMPANY
 705 4th National Bank Building
 Wichita, Kansas
 LOCATION: Tysor No. 1 NW SE 17-33S-7W, Harper Co, Kansas

Rotary Drilling Commenced 12-5-62
 Rotary Drilling Completed 12-22-62

CONTRACTOR: **PICKRELL DRILLING COMPANY**
Wichita, Kansas

CASING RECORD: (8 joints) 8 5/8" Surface Casing set at 215', cemented with 165 sacks cement. Circulated. Completed 6:15 P.M. 12-5-62. No oil string run, D & A.

LOG

(Figures indicate bottom of formation — measurements from top of rotary bushing.)

10	Sand	<u>C. F. S.</u>
215	Red Rock	3660
970	Red Rock & Shale	3710
1415	Shale & Shells - Anhydrite	4000
1660	Shale & Lime -- Anhydrite	4535
2245	Lime	4545
3455	Lime & Shale	4555
3640	Shale (Sandy) & Lime	4578
3805	Shale & Sand	4660
3930	Lime & Shale	4920
4165	Lime	4930
4375	Lime & Shale	4935
4425	Lime	4940
4500	Lime & Shale	4950
4535	Lime	4955
4847	Mississippi	4960
4935	Kinderhook	4968
4955	Kinderhook & Viola	4973
4973	Viola	5012
5012	Simpson - TD	

SLOPE TESTS

3700
 4105
 4300
 4982

S. L. M.

3900
 4400
 4800

RECEIVED
 STATE CORPORATION COMMISSION

DEC 28 1962

CONSERVATION DIVISION
 Wichita, Kansas

The undersigned, C. W. SEBITS, Attorney-in-Fact for PICKRELL DRILLING COMPANY, hereby certifies in behalf of said Company, that the above is a true and correct log of the formation encountered in drilling the above well as reflected by the Daily Drilling Reports.

PICKRELL DRILLING COMPANY

By C. W. Sebitts Attorney-in-Fact

STATE OF KANSAS }
 COUNTY OF SEDGWICK } ss.:

On this 26th day of December, 1962, before me the undersigned, a Notary Public, in and for the County and State aforesaid, personally appeared C. W. Sebitts, to me known to be the identical person who subscribed the name of PICKRELL DRILLING COMPANY to the foregoing instrument as its Attorney-in-Fact and acknowledged to me that he executed the same as his free and voluntary act and deed, and as the free and voluntary act and deed of such company, for the uses and purposes therein set forth.

Given under my hand and seal of office the day and year last above written.

My commission expires: June 21, 1966

Maxine Blackman
 Maxine Blackman Notary Public