


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Harper County, Sec. 12 Twp. 33 Rge. (E) 7 (W)
Location as "NE/CNW/SW" or footage from lines SW SW ME
Lease Owner Imperial Oil Co.
Lease Name Stout Well No. 1
Office Address 4th Natl. Bank Bldg.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-4-57 19
Application for plugging filed 9-4-57 19
Application for plugging approved 9-4-57 19
Plugging commenced 9-4-57 19
Plugging completed 9-4-57 19
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 5128 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------|--------|------------|
| | | | | 8 5/8 | 259 | 0 |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole w/mud to 250, 1/2 sack hulls, plug, 20 sacks cement. Filled hole w/mud to 35', 1/2 sack hulls, cement to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rupp-Ferguson Oil Co.
Address 522 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
L. W. Knox (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *L. W. Knox*
522 Union Center, Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of September, 19 57

My commission expires June 4, 1959 *Helen Horine* Notary Public.



PLUGGING
FILE SEC 12 T 33 R 7W
BOOK PAGE 43 LINE 34

SEP 17 1957
CONSERVATION DIVISION
Wichita, Kansas

15-077-00052-0000

CONTRACTOR'S WELL LOG

Imperial Oil Co. No. 1 Stout
SW SW NE, Sec. 12-33-7W,
Harper County, Kansas

Elevation 1393 RB
D & A

Commenced: 8-13-57
Completed: 9-4-57
Contractor: Rupp-Ferguson Oil Co.

Set 259' of 8 5/8" surface csg. w/170 sax

Figures Indicate Bottom of Formation

- 260 red bed & rock
- 610 red bed
- 1165 shale & shells
- 1265 lime & shale
- 1485 shale & shells
- 1928 lime & shale
- 1965 shale
- 2615 shale & shells
- 3290 shale & lime
- 3325 lime
- 3500 shale & lime
- 3585 shale & sand streaks
- 3620 shale & sand
- 3722 sand
- 3858 shale
- 3966 lime & shale
- 4120 lime
- 4389 lime & shale
- 4448 shale, lime & pyrite
- 4486 shale & lime
- 4742 Miss.
- 4781 lime, shale & sand
- 4800 cherty lime & shale
- 4920 lime & shale
- 4986 Simpson
- 5004 lime & shale
- 5083 lime, shale & sand
- 5128 Arb. T.D.

STATE OF KANSAS)
SEDGWICK COUNTY) SS:

SEP 17 1957

CONSERVATION DIVISION

I, L. W. Knox, Landman for Rupp-Ferguson Oil Co., ^{Wichita, Kansas} hereby certify that the above and foregoing is a true and correct copy of the log of the No. 1 Stout well.

L. W. Knox
L. W. Knox

Subscribed and sworn to before me this 9th day of September, 1957.

Helen Horine
Helen Horine, Notary Public

My Commission Expires June 4, 1959.

| | |
|--------------------------|--|
| PLUGGING | |
| FILE SEC. 12 T. 33 R. 7W | |
| BOOK PAGE 43 LINE 34 | |