

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Finney State Office Building
 30 South Market, Rm 2078
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-077-202190000

LEASE NAME MASON "B"

WELL NUMBER 1

1980 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 12 TWP. 33 RGE. 7 (E) or (W)

COUNTY HARPER

Date Well Completed 1-4-1974

Plugging Commenced 9-6-2000

Plugging Completed 9-7-2000

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-1-2000 (date)

by GARY WINTERS (KCC District Agent=s Name).

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation MISSISSIPPI Depth to Top 4472 Bottom 4485 T.D. 4524

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
MISSISSIPPI	OIL	4472	4485	8 5/8"	284	0
				4 1/2"	4524	2433

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. PMP 2 SXS HULLS & 15 SXS CMT @ 4472-4272. PULL FREE POINT & SHOOT OFF 4 1/2" CSG @ 2433. PMP 35 SXS CMT @ 1150-1050. PMP 35 SXS CMT @ 850-750. PMP 100 SXS FROM 335 TO SURF. CUT OFF AND CAP 4' BELOW GL.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 3118

Address RT 1 BOX 49BA, TYRONE, OK 73951-9731 PHONE: (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.


SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Shawn D. Young
 SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER


(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 27th day of October, 2000

My Commission Expires: _____



Notary Public



RECEIVED
 STATE CORPORATION COMMISSION

OCT 31 2000

CONSERVATION DIVISION
 Wichita, Kansas