

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 Finney State Office Building
 130 South Market, Rm 2078
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-077-20,201

LEASE NAME HAYTER "A"

WELL NUMBER 1

660 Ft. from N Section Line

1980 Ft. from W Section Line

SEC. 12 TWP. 33S RGE 07 (E) or (W)

COUNTY HARPER

Date Well Completed 08/14/73

Plugging Commenced 05/05/97

Plugging Completed 05/12/97

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well GAS

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 04/21/97 (date)

by MR. STEVE VANGEISON (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation MISSISSIPPI Depth to Top 4477' Bottom 4499' T.D. 4499'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
MISSISSIPPI	GAS	4477'	4499'	8-5/8"	284'	3'
				4-1/2"	4477'	3624'

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. MIRU PU. TOH W/TBG LAYING DWN. PMPD 1 SK HULLS & 20 SKS CMT. DISPLACE TO 4200' W/9 PPG MUD. RAN FREE PT & SHOT OFF CSG @ 3624'. TOH W/1000' OF 4-1/2" CSG. TOH W/ 1500' OF 4-1/2" CSG. PMPD 35 SXS CMT @ 1150'. PULLED CSG TO 800' & PMPD 35 SXS OF CMT. RIH W/WIRELINE. TAG TOC @ 30. PMPD 10 SKS CMT TO FILL HOLE. CUT OFF 8-5/8" CSG & CAPPED 3' BELOW GL. WITNESSED BY KCC REP STEVE VANGEISON.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT. 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE: (405) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) John A. Broman


JOHN A. BROMAN, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 6th day of June, 1997

Shirley J. Childers
 Notary Public

My Commission Expires: 11/14/98



RECEIVED
 AS COMP COM
 JUN-9 11:15