

LEASE NAME Peavey

WELL NUMBER SWD

SPOT LOCATION SW SW SW

SEC. 14 TWP. 11 RGE. 18 (E) or (W)

COUNTY Ellis

Date Well Completed 1-7-52

Plugging Commenced 7-31-89

Plugging Completed 7-31-89

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Okmar Oil Company

ADDRESS Box 723 Hays, Kansas 67601

PHONE # (913) 628 6101 OPERATORS LICENSE NO. 5245

Character of Well SWD
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office of this well? Yes

Which KCC/KDHE Joint Office did you notify? Hays, Kansas District 4

Is ACO-1 filed? If not, is well log attached?

Producing formation Depth to top bottom T.D. 4042

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
	Surface	0	216	8 5/8		None
	Casing	0	4042	5 1/2		None
	Cement lined		2600	3"		

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state the character of same and depth placed, from feet to feet each set. Run tubing to 2500' and mix 100 sks. 60/40 pos, 8% gel. Circulate. Pull 1400' tubing. Mix 60 sks. cement. Circulate. Pull rest tubing. Mix rest cement pump down 5 1/2 casing. Total 200 sks. Close in 150#.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Okmar Oil Company License No. 5245
 Address Box 723 Hays, Kansas 67601


BJ Titan cement

STATE OF Kansas COUNTY OF Ellis, ss.

Mr. Ted Crawford (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Ted Crawford
 (Address) Box 723 Hays, KS

SUBSCRIBED AND SWORN TO before me this 5 day of August, 1989



Rosemary Smith
 Notary Public

My Commission expires: 5/1/1991