

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 North Market, Insurance Bldg.
Wichita, Kansas

Al

WELL PLUGGING RECORD

Ellis County, Sec. 14 Twp. 11 Rge. (E) 18W (W)

Location as "NE/CNW&SW" or footage from lines. NE SE SE

Lease Owner Nadel & Gussman

Lease Name Lynn Well No. # 1

Office Address 1/2 Ralph Reaves Plainville Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 1-5-61 19

Application for plugging approved yes 19


Plugging commenced 1-12-61 19

Plugging completed 1-16-61 19

Reason for abandonment of well or producing formation:

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Eldon Petty

Producing formation Depth to top Bottom Total Depth of Well 3466 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 5 1/2" | | 2,637' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugging commenced 1-12-61. Plugging completed 1-16-61.

Measured in to total depth, 3466'.

Plugged off bottom: Sanded back from 3466' to 3440' and dumped 4 sacks of cement.

Worked and shot casing. Worked and shot 5 1/2" casing free at 2,637'. Built rack and slide. Pulled and layed down casing.

Plugged well: Pumped mud up to 400' and spotted 25 sacks of cement at 400'. Pumped mud up to 200' and spotted 25 sacks of cement at 200'. Mudded hole up to top and set rock bridge and capped the well with 10 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION

FEB 16 1961

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J. O. Forbes d/b/a Forbes Casing Pulling Company CONSERVATION DIVISION

Address P. O. Box 221 Great Bend, Kansas Wichita, Kansas

STATE OF Kansas COUNTY OF Barton, ss.

J. O. Forbes

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) J. O. Forbes

J. O. Forbes
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 23rd day of January, 1961

My commission expires December 8th, 1963

Kayann Jenkins Notary Public.



LYON #1
SE 1/4 of Section 14-11S-18W
Ellis County, Kansas.
Herbert Gussman

15-051-05245-0000

Commenced: March 12, 1943
 Completed: April 18, 1943

| | | |
|----------------------------|------|------|
| Surface rock and clay | 0 | 88 |
| Blue shale | 88 | 290 |
| Shale and shells | 290 | 328 |
| Sand and lime | 328 | 400 |
| Shale and lime | 400 | 510 |
| Sand | 510 | 530 |
| Shale | 530 | 560 |
| Sand | 560 | 588 |
| Shale and shells | 588 | 574 |
| Iron | 574 | 581 |
| Shale | 581 | 687 |
| Sand | 687 | 810 |
| Shale and shells | 810 | 850 |
| Sand | 850 | 840 |
| Shale and shells | 840 | 918 |
| Shale | 918 | 980 |
| Lime | 980 | 1018 |
| 2nd bed | 1018 | 1040 |
| Arg. bed and shale | 1040 | 1178 |
| Anhydrite | 1178 | 1217 |
| Shale and shells | 1217 | 1776 |
| Lime and shale | 1776 | 2168 |
| Lime | 2168 | 2270 |
| Shale and lime shells | 2270 | 2348 |
| Lime and shale | 2348 | 2430 |
| Broken lime | 2430 | 2525 |
| Lime | 2525 | 2570 |
| Shale and shells | 2570 | 2670 |
| Broken lime | 2670 | 2740 |
| Shale | 2740 | 2780 |
| Lime | 2780 | 2825 |
| Lime and junk | 2825 | 2930 |
| Junk, lime and shale | 2930 | 2945 |
| Lime | 2945 | 2980 |
| Lime and shale | 2980 | 3080 |
| Lime | 3080 | 3095 |
| Shale and lime | 3095 | 3165 |
| Lime w/small streaks shale | 3165 | 3195 |
| Lime | 3195 | 3323 |
| Lime and shale | 3323 | 3364 |
| Lime | 3364 | 3379 |
| Conglomerate | 3379 | 3429 |
| Shale | 3429 | 3448 |
| Simpson sand | 3448 | 3453 |
| Arbuckle lime | 3453 | 3450 |
| Lime | 3450 | 3458 |
| TOTAL DEPTH | 3458 | |

CASING RECORD

3-5/8" Surface Casing set at 1198' and cemented with 525 sacks of cement.

5-1/2" O. D. Casing set at 3454' and cemented with 125 sacks of cement.

5'2" 15# H-40

RECEIVED
 STATE CORPORATION COMMISSION

JAN 6 1961

CONSERVATION DIVISION
 Wichita, Kansas

STATE OF OKLAHOMA)
)
 COUNTY OF TULSA)

I hereby affirm that the above and foregoing is a true and correct copy of the log of your Lyon Well #1, located in the Southeast Quarter of Section 14, Township 11 South, Range 18 West, Ellis County, Kansas.

HELMERICH & PAYNE, INC.

BY _____
 Treasurer

Subscribed and sworn to before me, a Notary Public, this 21st day of April, 1943.

 Notary Public

My commission expires July 22nd, 1943