

API NUMBER None

LEASE NAME Lynn

WELL NUMBER 1

2310 Ft. from S Section Line

330 Ft. from E Section Line

SEC. 14 TWP. 11S RGE. 18 (D) or (W)

COUNTY Ellis

Date Well Completed 7-24-41

Plugging Commenced 12-10-87

Plugging Completed 12-10-87

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Kaiser-Francis Oil Company

ADDRESS P. O. Box 21468, Tulsa, OK 74121-1468

PHONE# (918) 494-0000 OPERATORS' LICENSE NO. 6568

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well).

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? District #4, Hays

Is ACO-1 filed? on old form If not, is well log attached? -

Producing Formation LKC Arbuckle Depth to Top 2986 Bottom 3154 T.D. 3362
3353

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
LKC	Oil	2986	3154	8-5/8	1127	-0-
Arbuckle	Oil	3353	62	4-1/2	3353	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Perf'd 4-1/2" @ 1126' & 595'. Pumped 250 sxs thrifty-mix + 800# hulls from 3362'-surface.

JOB COMPLETE

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kaiser-Francis Oil Company License No. 6568

Address P. O. Box 21468, Tulsa, OK 74121-1468

STATE OF Oklahoma COUNTY OF Tulsa, ss.

Charlotte Van Valkenburg (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) C. Van Valkenburg

(Address) P. O. Box 21468, Tulsa, OK 74121

SUBSCRIBED AND SWORN TO before me this 30th day of December, 19 87

Deborah L. Hurrell
 Notary Public

RECEIVED
 My Commission Expires 12-6-89
 STATE CORPORATION COMMISSION



JAN 07 1988