

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 30 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Jack Richardson of Slawson Drilling Co., Inc., has this date requested permission to plug the following described well:

Mr. Richardson guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson,

Complete Address: 408 One-Twenty Building, Wichita, Kansas.

Lease Name: Mellies Well No. E-1

Location: SE-NW-SE Sec. 20 Twp. 19 Rge. (E)(W) 24

County: Ness Total Depth 4432' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Richardson was instructed to plug the well as follows:

350'--8 5/8" Surface casing, cement circulated.

Circulate hole with heavy mud. Pull DP to 850' and displace 80 Sx. cement thru DP. Pull DP to 310' and displace 35 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 15 Sx. cement to cellar.

Very truly yours,

M. L. Nichols

Conservation Division Agent