

15.135-20931-0000

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 2 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Cameran of H-30 Drlg. has this

date requested permission to plug the following described well:

Mr. Cameran guarantees payment of the plugging fee.

Operator's full Name: F. & M Oic Co., Inc.

Complete Address: 603 Union Center, Wichita, Ks.

Lease Name: Davison ~~XXXXXXXX~~ Well No. 1

Location: SW SE Sec. 9 Twp. 19 Rge. (E)(W) 24

County: Ness Total Depth 4385' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Cameran was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 70 sk cmt plug at 550' thru drill pipe.

Heavy mud to 185' & set 20 sk cmt plug thru drill pipe. Heavy mud to

40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Rev. F. Messert
Conservation Division Agent