

1 01032

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,857 0000
E/2, W/2 W/2, SEC. 31, T. 7, R. 26 S, R. 12 W/SX
2640 feet from S section line
4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9408
Operator: Trans Pacific Oil Corporation
Name & Address: One Main Place, Ste...1000
Wichita, KS 67202

Lease Name Honeman Well # 1
County Pratt
Well Total Depth 4312 140.14 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 328

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 11:15 a.m. Day: 25 Month: 2 Year: 19 94

Plugging proposal received from Vernon Duntz Jr.
(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

Perfs: 5 1/2" at 4302' w/175 sx cement, Perfs at 4301-13'
1st plug sand back to 4250' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 10 3/4"
wiper plug and pump 175 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 12:15 p.m. Day: 25 Month: 2 Year: 19 94

ACTUAL PLUGGING REPORT 1st plug sanded back to 4250' and dumped 5 sx cement on top of sand
bridge through bailer,
2nd plug pumped down 10 3/4" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel,
100 lbs. hulls, released 10 3/4" wiper plug and pumped 175 sx cement.
Maximum pressure 200 psi and shut in 75 psi.

RECEIVED STATE CORPORATION COMMISSION

MAR 02 1994

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2800' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form. CONSERVATION DIVISION
Wichita, Kansas)

I told / ~~XXXXXX~~ observe this plugging.

Signed *Steph...* (TECHNICIAN)

40085