

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-095-201683-0000

NW NW, SEC. 10, T 29 S, R 6 (W)

4620 feet from (S) section line

4620 feet from (E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Brown Well # D-1

Operator: TXO Prod Corp.

County Kingman 132.63

Name & Address 200 W Douglas #300

Well Total Depth 4081 feet

Wichita Ks 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 269

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service License Number _____

Address Pratt Ks.

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Jerry Whitted

(company name) TXO (phone) _____

were: _____

4 1/2 4076 Sand to 3989' 5 sks. **RECEIVED**

OH 4076-81 3hull 15 gel 30sk Plus 80sk STATE CORPORATION COMMISSION

APR 11 1986

CONSERVATION DIVISION
Wichita, Kansas

Plugging Proposal Received by Stan Marcotte
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 1430 Day: 21 Month: 3 Year: 19 86

ACTUAL PLUGGING REPORT The open hole was sand back to 3989 and
5 sks of cement dumped on the sand. The 4 1/2 was shot off
and recovered from 3028'. The Tap was squeezed by
pumping down the 8 5/8" 3 sks of hulls, 15 sks of gel, 30 sks of
cement as wiper plug and 80 sks of cement.

Remarks: D.S. Titan 283222 MX 750 ET 500

(If additional description is necessary, use BACK of this form.)

I (did) did not observe this plugging.

Signed Stan VanBeem
(TECHNICIAN)

WT

80