

To: 1
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

DEC 15 1988
API NUMBER 15- 007-21,289 0000
100' N of
NW NW SW, SEC. 22, T 32 S, R 14 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

2410 feet from S section line

4950 feet from E section line

Operator: Texas Energies, Inc.

Lease Name Hoagland Well # 1-22

Name & Address P.O. Box 947

County Barber 169.33

Well Total Depth 5210 feet

Pratt, KS 67124

Conductor Pipe: Size 16" feet 48'

Surface Casing: Size 8 5/8" feet 885'

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Pratt Well Service Inc. License Number 5893

Address Box 847, Pratt, KS 67124

Company to plug at: Hour: 11:30 a.m. Day: 15 Month: 12 Year: 19 88

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service Inc. (phone) 316-672-2531

were: 4 1/2" at 4843' PBTB 4800' Perfs at 4642-56'

1st plug pump 4 1/2" with 200 lbs.hulls.and 25 sx Class A cement,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

Plugging Proposal Received by James R. Kapp

(TECHNICIAN)

Plugging Operat/Conservation Division tended by Agent?: All X Part _____ None _____

Operation Wichita, Kansas Hour: 12 p.m. Day: 15 Month: 12 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 4 1/2" with 200 lbs. of hulls and 25 sx common cement,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 100 lbs. hulls,

and 100 sx cement.

Maximum pressure 100 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 3757' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

observe this plugging.

DATE DEC 22 1988

INV. NO. 23454

Signed Stephen J. Pfeiffer
(TECHNICIAN)

12-15

500