

To: 1  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-22,710-000 *R*  
SW NW <sup>NE</sup> ~~SE~~, SEC. 13, T. 17 S, R. 26 W/E  
1650 <sup>ANDYCC</sup> feet from S section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5923  
Operator: American Petroleum Co., Inc.  
Name & Address 400 North Woodlawn, Suite 111  
Wichita, KS 67208

2310 feet from E section line  
Lease Name Quenzer Well # 1-B  
County Ness 145.67  
Well Total Depth 4482 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 303

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Hembree Well Service License Number 6907

Address Box 458, Ness City, KS 67560

Company to plug at: Hour: 4:30 pm Day: 29 Month: August Year: 19 85

Plugging proposal received from Daryl John

(company name) Hembree Well Service (phone) 913-798-3408

were: 5 1/2" at 4478' PBDT 4450' Perfs at 4433.5' - 4437.5' 4425-4427'

1st plug sand back to 4375' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, release 8 5/8"

rubber plug and pump 110 sx cement.

Plugging Proposal Received by Don C. Ubel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 6:00 pm Day: 29 Month: August Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4375' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel and 110 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 6 1985

Maximum pressure 200 psi and shut in 50 psi

Remarks: Recovered 2285' 5 1/2" casing. Used 60/40 Pozmix 6% gel by All Well Co., Kansas  
(If additional description is necessary, use BACK of this form.)

INVOICED  
Observe this plugging.

DATE SEP 10 1985  
INV. NO. 990

Signed Don Gooden  
(TECHNICIAN)