

To: 1
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

10-22 API NUMBER 15-135-22,302-00-00

E/2 SW SE, SEC. 13, T 17 S, R 26 W/E
660 feet from S section line
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 30742

Lease Name Quenzer Well # 2

Operator: Palomino Petroleum, Inc.
Name & Address 4924 SE 84th St.
Newton, KS 67114-8827

County Ness 143.98
Well Total Depth 4430 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 287

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901
Address P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 9:30 a.m. Day: 22 Month: 10 Year: 19 97

Plugging proposal received from Klee Watchous
(company name) Palomino Petroleum, Inc. (phone) 316-799-1000

were: 5 1/2" at 4417', Open hole 4417-4430'
1st plug sand back to 4365' and dump 5 sx cement on top of sand through bailer,
2nd plug circulate from free point to surface with cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 22 Month: 10 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 4380' and dumped 5 sx cement on top of sand through bailer,

2nd plug circulated from 525' to surface with 140 sx cement and 100 lbs. hulls.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 525' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

Signed Michael Maier
(TECHNICIAN)

49377