

To: 107  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- NA 15-135-0032400-01

C. SE. SW, SEC. 13, T. 17 S, R. 26 W/E

660 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5161

Lease Name Klement "B" Well # 1

Operator: Palomino Petroleum

County Ness

Name & Address

Rt. 5, Box 51-C

Well Total Depth 4530 feet

Newton, KS 67114

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 240

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Palomino Petroleum License Number 5161

Address Rt. 5, Box 51-C, Newton, KS 67114

Company to plug at: Hour: 1:15 p.m. Day: 27 Month: 10 Year: 1987

Plugging proposal received from Deacon Pulley

(company name) Rockhold Engineering (phone) 316-792-2506

were: 5 1/2" at 4529' BPTD 4481' Perfs at 4435-46, 4448-54' Elevation 2494' KB

1st plug sand back to 4380' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx cement, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 150 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 2:30 p.m. Day: 27 Month: 10 Year: 1987

ACTUAL PLUGGING REPORT 1st plug sanded back to 4380' and dumped 5 sx cement on top of sand through bailer,

2nd plug ran tubing to 1210', circulated cement to surface, pulled tubing and topped off well. Used 450 lbs. hulls and 150 sx ATL cement.

RECEIVED  
STATE CORPORATION COMMISSION

OCT 29 1987

Remarks: Used ATL cement by Allied. Recovered 2500' of 5 1/2" casing.

If additional description is necessary, use BACK of this form. CONSERVATION DIVISION  
Wichita, Kansas

**INVOICED**

(old / ~~XXXXXX~~) observe this plugging.

DATE 11-4-87

Signed Dan Goodson  
(TECHNICIAN)

INV. NO. 18744