

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-22,367-00-00

SW SW SW, Sec. 14, T 17 S, R 26 W/D

330 feet from N/S section line

330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6113

Lease Name Hopkins Well # 1

Operator: Landmark Oil Exploration  
Name & Address 105 S. Broadway, Suite 1040  
Wichita, Kansas 67202

County Neosho

Well Total Depth 4487' feet 145.83

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 1/2" feet 325

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Red Tiger Drilling Co. License Number 5302

Address 1720 Kansas State Bank Bldg. Wichita Kansas 67202

Company to plug at: Hour: 6:00 P.M. Day: 15 Month: March Year: 1983

VERBAL PLUGGING ORDERS GIVEN TO Bruce Fricke

(company name) Red Tiger Drilling Co. (phone) \_\_\_\_\_

were: 1st plug @ 1860' w/ 50 sbx cement. 2nd plug @ 900' w/ 50 sbx cement. 3rd plug @ 330' w/ 40 sbx cement. 4th plug @ 40' on solid bridge w/ 10 sbx cement filling hole to 0. Circulate the rat hole w/ 10 sbx cement. Halliburton cementing accomplished the plugging w/ 50/50 gypsum w/ 4 1/2 gal 3% C.C.

Signed Paul A. Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 9:15 P.M. Day: 15 Month: March Year: 1983

ACTUAL PLUGGING REPORT This hole was plugged as orders given in above paragraph.

Remarks: Mr. Steve Durron gave the orders.

I hereby certify that the above plugging instructions were given as herein stated and that I (~~did~~ / did not) observe this plugging.

4-8-83  
3922-W  
RECEIVED  
STATE CORPORATION COMMISSION  
MAR 21 1983  
CONSERVATION DIVISION  
Wichita, Kansas

Signed Paul A. Luthi  
(TECHNICIAN)