

21 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-23,066-0000  
SW SW SW SEC. 21, T 17 S, R 26 W/E  
440 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5005

Lease Name Miner Well # 1

Operator: Sunburst Exploration Company, Inc. County Ness

145.60

Name & Address 112 Corporate Place, 125 N. Emporia  
Wichita, KS 67202

Well Total Depth 4480 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 302

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Blue Goose Drilling Co., Inc. License Number 5104

Address Box 1413, Ste 2C, Broadway at Main, Great Bend, KS 67530

Company to plug at: Hour: 1 p.m. Day: 5 Month: 11 Year: 19 86

Plugging proposal received from Martin Miller

(company name) Blue Goose Drilling Co., Inc. (phone) 316-264-0216

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2454' GL  
Anhydrite 1830'

1st plug at 1850' with 50 sx cement, 2nd plug at 1240' with 80 sx cement,  
3rd plug at 300' with 40 sx cement, 4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 10 sx cement,

Plugging Proposal Received by Jack Luthi  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:15 p.m. Day: 5 Month: 11 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1830' with 50 sx cement,

2nd plug at 1020' with 80 sx cement,

3rd plug at 330' with 40 sx cement,

4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement. NOV 10

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
(If necessary) observe this plugging.

DATE 11-12-86

Signed Dan Horkow  
(TECHNICIAN)

INV. NO. 15335  
11-5

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date October 31 1986 month day year

API Number 15- 135-23,066-0000
SW SW SW Sec. 21 Twp. 17 S, Rg. 26
440 Ft. from South Line of Section
4950 Ft. from East Line of Section

OPERATOR: License # 5005
Name Sunburst Exploration Company, Inc.
Address 112 Corporate Place, 125 N. Emporia
City/State/Zip Wichita, Kansas 67202
Contact Person Ronald L. Irion
Phone (316) 262-3041

Nearest lease or unit boundary line 330 feet
County Ness
Lease Name Miner Well # 1
Ground surface elevation 2454 feet MSL
Domestic well within 330 feet: yes X no
Municipal well within one mile: yes X no
Surface pipe by Alternate: 1 2 X
Depth to bottom of fresh water 100
Depth to bottom of usable water 1025
Surface pipe planned to be set 280
Projected Total Depth 4550 feet
Formation Mississippian

CONTRACTOR: License # 5104
Name Blue Goose Drilling Co., Inc.
City/State Great Bend, Kansas 67530

Well Drilled For: Well Class: Type Equipment:
X Oil SWD Infield X Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expt X Wildcat Cable

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.

Date 10-17-86 Signature of Operator or Agent Ronald L. Irion Title Vice President

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 200 feet per Alt.
This Authorization Expires 4-17-87 Approved By 10-17-86

SPUD - 10-27-86 (4:00 PM)

SP = 280 +

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call a.m. to 5 p.m. workdays).

Table with columns for plug depth, feet depth with, and sxs of. Includes entries for 1st plug @ 1850, 2nd plug @ 1240, 3rd plug @ 300, 4th plug @ 40, 5th plug @ 10, and Rathole with 10.

Vertical list of well parameters: FUSHER, TD 4500 FORMATION Miss, SURFACE PIPE 5 5/8 @ 302, ANHYDRITE 1830 ELEVATION 2454 G.L., STARTING TIME & DATE, COMPLETION TIME & DATE, 1st PLUG @ 1830 FT. W/ 50 SX, 2nd PLUG @ 1020 FT. W/ 80 SX, 3rd PLUG @ 330 FT. W/ 40 SX, 4th PLUG @ 40-0 FT. W/ 10 SX, RAT HOLE CIRCULATED W/ 15 SX, MOUSE HOLE CIRCULATED W/ SX, WATER WELL PLUGGED W/ SX, CEMENT COMPANY, TECHNICIAN Early Am - Will Call Handrow Early Am 11-4-86

NOV 10 1986