

1060112

7-16

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
WICHITA STATE OFFICE BUILDING  
WICHITA, KANSAS 67202

API number: 15-135-23,917-~~0000~~

NE NW NE SEC. 23, 17 S, 26 W  
4950 feet from S section line  
1650 feet from E section line

RECEIVED  
JUL 23 1998  
CONSERVATION DIVISION  
Wichita Kansas

Operator license#5123

Lease Bauer Trust "J" well#4

Operator: Pickrell Drilling

County Ness

144.79

Address: 110 N Market, Ste 205  
Wichita, KS 67202

Well total depth 4455 feet  
Conductor Pipe: inch @ feet  
Surface pipe: 8 5/8 inch @ 225 feet  
Production Csg: 4 1/2 inch @ 4453 feet

Aband. Oil well X, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Allied Cementing Co, Inc License# N/A

Address: PO Box 628, Great Bend, KS 67530

Company to plug at: Hour: 9:15 a.m. Day: 16 Month: July Year: 1998

Plugging proposal received from: Ed Mondero

Company: Allied Cementing, Co, Inc Phone: 316-793-5861

Were: Perforated at 4601-4603. 1<sup>st</sup> plug circulate 105 sx cement from 1800' to surface through 2 3/8 tubing and top off with 10 sx cement, pull tubing out of hole. Check backside, pump in 10 sx cement down backside, shut in pressure 500 #.

Plugging Proposal Received by: Michael Maier

Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 12:30p.m. Day: 16 Month: July Year: 1998

Actual plugging report:

1<sup>st</sup> plug with 15 sx cement and 50# hulls,  
2<sup>nd</sup> plug circulate 105 sx cement from 1800' to surface through 2 3/8 tubing and top off with 10 sx cement, pull tubing out of hole. Check backside, pump in 10 sx cement down backside, shut in pressure 500#.

Remarks: Used 60/40 Pozmix 6% gel by Allied No casing recovery.

I did  /did not  observe the plugging.

Michael J. Maier

(agent)

Form CP-2/3

INVOICED

DATE JUL 30 1998

INV. NO. 51053