

To: 1
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-135-23,924-00-00
SW SW NW, SEC. 23, T 17 S, R 26 W X
2310 feet from N S section line
330 feet from W E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5123
Operator: Pickrell Drilling Company, Inc.
Name & Address 110 N. Market, Ste. 205
Wichita, KS 67202

Lease Name Norton Z Well # 1
County Ness
Well Total Depth 4490 145.93 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 230

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SMD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Pickrell Drilling Company, Inc. License Number 5123
Address 110 N. Market, Ste. 205, Wichita, KS 67202

Company to plug at: Hour: 10 p.m. Day: 1 Month: 2 Year: 1996

Plugging proposal received from Doyle Folkerts
(company name) Pickrell Drilling Company, Inc. (phone) 316-262-8427

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1820-55'
1st plug at 1860' with 50 sx cement, 2nd plug at 1200' with 80 sx cement,
3rd plug at 600' with 40 sx cement, 4th plug at 270' with 40 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

RECEIVED
KANSAS CORP COM
996 FEB - 7 12:44:19 '96

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None _____

Operations Completed: Hour: 12 a.m. Day: 2 Month: 2 Year: 1996

ACTUAL PLUGGING REPORT 1st plug at 1860' with 50 sx cement,
2nd plug at 1200' with 80 sx cement,
3rd plug at 600' with 40 sx cement,
4th plug at 270' with 40 sx cement,
5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 2# Floseal by Allied.
(If additional description is necessary, use BACK of this form.)

I (~~XXXX~~) did not observe this plugging.

Signed Duane Rankin
(TECHNICIAN)

2-28-96
44904
2-3

FOR KCC USE:

FORM C-1 7/91

EFFECTIVE DATE: 1-21-96

State of Kansas

FORM MUST BE TYPED
FORM MUST BE SIGNED

DISTRICT # 11
SCA? Yes No

NOTICE OF INTENTION TO DRILL 135-23, 924-00-00 ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 01 - 22 - 96
month day year

Spot SW - SW - NW Sec 23 Twp 17S S, Rg 26 East X West

OPERATOR: License # 5123
Name: Pickrell Drilling Company, Inc.
Address: 110 N. Market, Suite 205
City/State/Zip: Wichita, Kansas 67202
Contact Person: Larry J. Richardson
Phone: 316-262-8427

2310 feet from South North line of Section
330 feet from East West line of Section
IS SECTION X REGULAR IRREGULAR?

(NOTE: Locate well on the Section Plat on Reverse Side)

CONTRACTOR: License #: 5123
Name: Company Tools

County: Ness
Lease Name: Norton "Z" Well #: 1
Field Name: Kansada

Is this a Prorated/Spaced Field? yes X no
Target Formation(s): Mississippian

Nearest lease or unit boundary: 330'
Ground Surface Elevation: 2485' est. feet MSL

Water well within one-quarter mile: yes X no
Public water supply well within one mile: yes X no

Depth to bottom of fresh water: 180'
Depth to bottom of usable water: 1200'

Surface Pipe by Alternate: 1 X 2
Length of Surface Pipe Planned to be set: 200'+

Length of Conductor pipe required: N/A
Projected Total Depth: 4500'

Formation at Total Depth: Mississippian
Water Source for Drilling Operations:

... well ... farm pond X other
DWR Permit #: ...
Will Cores Be Taken? ... yes X no

If yes, proposed zone: ...

Well Drilled For: Well Class: Type Equipment:
Oil Enh Rec Infield X Mud Rotary
Gas Storage X Pool Ext. Air Rotary
OAWO Disposal Wildcat Cable
Seismic; # of Holes Other
If OAWO: old well information as follows:
Operator: ...
Well Name: ...
Comp. Date: ... Old Total Depth ...

Directional, Deviated or Horizontal wellbore? ... yes X no
If yes, true vertical depth: ...
Bottom Hole Location: ...

AFFIDAVIT

200' Alt. II Req.

Exp. 7/16/96

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Payler
SPUD DATE 1-22-96 INIT. SH
LENGTH SURFACE PLANNED 230
RESERVE PIT STATUS- REMOVE FLUID LINED
after salt sect. bbls. when done bbls.
RATHOLED AHEAD? Y N SIZE HOLE
SURFACE PIPE 8 1/2 @ 230 CONDUCTOR
ANHYDRITE T- 1820 B- 1825 ELEVATION
4444 leading
TD @ 2190 FORMATION
RAN PIPE @ DV TOOL ALT II DONE
SX Y N
Arbuckle Plug @ Ft. W/ SX
Hng./Council @ Ft. W/ SX
Anhydrite Base @ 1860 Ft. W/ 50 SX
1/2 Base Anyh. @ 1200 Ft. W/ 80 SX
1/2, 1/2 Plug @ 600 Ft. W/ 40 SX
Bottom Surface @ 280 Ft. W/ 40 SX
40' Plug @ 40 Ft. W/ 10 SX
RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX
WATER WELL SX (Irr. Well Pond Hauling)
TECHNICIAN GR DATE 1-31-96
TYPE OF CEMENT 100-50-70 2 To 45 and
STARTING TIME 10:00 (AM/PM) DATED 1-1-96
COMPLETION TIME 12:00 (AM/PM) DATED 1-1-96
CEMENT COMPANY Attila