

100000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,588-00-00
C SW NW, SEC. 7, T 18 S, R 22 WPA

TECHNICIAN'S PLUGGING REPORT

1980 feet from N/SX section line
660 feet from W/EX section line

Operator License # 6875

Lease Name Stenzel Well # 12-7

Operator: Marmik Oil Company

County Ness

Name & Address 910 16th Street, Suite 200

Well Total Depth 4310 140.08 feet

Denver, CO 80202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 455

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Warrior Drilling Co. License Number 5883

Address 905 Century Plaza, Wichita, KS 67202

Company to plug at: Hour: Noon Day: 5 Month: June Year: 1984

Plugging proposal received from Marion Burris

(company name) Warrior (phone) 316-653-7716

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1530' with 50 sx cement

2nd plug at 840' with 50 sx cement

3rd plug at 500' with 40 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement
Plugging Proposal Received by Richard W. Lacy
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part X None _____

Operations Completed: Hour: 2:30 pm Day: 5 Month: June Year: 1984

ACTUAL PLUGGING REPORT 1st plug at 1530' with 50 sx cement, 2nd plug at 840' with 50 sx cement, 3rd plug at 500' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 15 sx cement, 7th plug to circulate mouse hole with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
06-07-1984
JUN 07 1984

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Allied.
(If additional description is necessary, use BACK of this form.)

I (did / ~~did not~~) observe this plugging.

6-13-84

Signed Richard W. Lacy
(TECHNICIAN)

2052
1-5