

To: 1
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-22,822-00-00
NW SE NW, SEC. 3, T 18 S, R 22 W/E
3630 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4174

Lease Name Reis Well # 1-3

Operator: Western Oil Corporation

County Ness 140.40

Name & Address Box 15277

Well Total Depth 4320 feet

Lakewood, CO 80215

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 639

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Plains Inc. License Number 4072

Address Box 346, Ness City, KS 67560

Company to plug at: Hour: 3 p.m. Day: 14 Month: 11 Year: 19 88

Plugging proposal received from Clint Base

(company name) Plains Inc. (phone) 913-798-3995

were: 5 1/2" at 4319' PBT 4290' Perfs at 4263-70'

1st plug sand back to 4200' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, and 100 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4 p.m. Day: 14 Month: 11 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded back to 4200' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 sx

Maximum pressure 400 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 1483' of 5 1/2" casing
(If additional description is necessary, use BACK of this form.)

(and) observe this plugging.

Signed Dan Goodrow
(TECHNICIAN)

DATE 11-29-88

INV. NO. 23163

11-14

STATE CORPORATION COMMISSION
RECEIVED
NOV 13 1988
11-18-1988
CONSERVATION DIVISION
Wichita, Kansas