

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-135-22,606-0000

LEASE NAME Johnson "A"

WELL NUMBER 1

SPOT LOCATION 215' W of
N/2 N/2 NW

SEC. 18 TWP. 17 RGE. 26 (E) or (W)

COUNTY Ness

Date Well Completed 6-18-84

Plugging Commenced 6-18-84

Plugging Completed 6-18-84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR D. R. Lauck Oil Company, Inc.

ADDRESS 221 S. Broadway, Suite 400, Wichita, Kansas 67202

PHONE # (316) 263-8267 OPERATORS LICENSE NO. 5427

Character of Well D&A
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? #1, Dodge City, Kansas

Is ACO-1 filed? To be filed. If not, is well log attached? Yes

Producing formation _____ Depth to top _____ bottom _____ T.D. 4585'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
		0'	337'	8-5/8"	330.85'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

(Used 60-40 Pozmix Cement, 2% Gel, 3% Calcium Chloride)

Plugged with 50 sacks cement at 1950';

50 sacks cement at 780'; 40 sacks cement

at 360'; solid bridge plug and 10 sacks

cement at 40'; and 10 sacks cement in rat hole.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co. License No. _____
Address Box 31, Russell, Kansas 67665

STATE OF KANSAS COUNTY OF SEDGWICK, ss.

John D. Knightley (employee of operator) or
(operator) of above-described well, being first duly sworn on oath, says: That
I have knowledge of the facts, statements, and matters herein contained and
the log of the above-described well, as filed that the same are true and
correct, so help me SEATE CORPORATION COMMISSION


(Signature) [Signature]
(Address) 221 S. Broadway, Suite 400
Wichita, Kansas 67202

JUN 28 1984

CONSERVATION DIVISION
Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 27th day of June, 1984

Stella J. Lips
Notary Public



15-135-22606-0000

D. R. Lauck Oil Company, Inc.
221 S. Broadway, Suite 400
Wichita, Kansas 67202

- Johnson "A" #1
215' W of N/2 N/2 NW
Section 18-17S-26W
Ness County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.
221 S. Broadway, Suite 400
Wichita, Kansas 67202

Commenced: June 7, 1984
Completed: June 18, 1984

Drillers Log

Shale	1440
Sand	1675
Shale & Shells	1949
Anhydrite	1980
Shale	2560
Shale & Lime	3565
Lime	4585 RTD

Casing: 337' 8-5/8" cemented with 190 sacks 60-40 Pozmix Cement,
2% Gel, 3% Calcium Chloride.

RECEIVED
STATE CORPORATION COMMISSION

JUN 28 1984

CONSERVATION DIVISION
Wichita, Kansas