STATE OF KANSAS
STATE CORPORATION COMMISSION


15-135-20635-0000

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Ness County. Sec. 21 Twp. 17S Rge. ____ (E) 26 (W)

Location as "NE/CNW¼SW¼" or footage from lines NW NE NW

Lease Owner Thunderbird Drilling, Inc.

Lease Name Miner "I" Well No. 1

Office Address 4328 East Kellogg, Wichita, Kansas 67218

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed July 9 19 72

Application for plugging filed July 9 19 72

Application for plugging approved July 9 19 72

Plugging commenced July 9 19 72

Plugging completed July 9 19 72

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production ____ 19 ____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas

Producing formation ____ Depth to top ____ Bottom ____ Total Depth of Well 4528 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS — CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	341.59'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ____ feet to ____ feet for each plug set.

Plugged hole as follows: Plugged at 720' with 70 sacks of regular cement; plugged at 300' with 20 sacks of regular cement; plugged at 40' with 10 sacks of regular cement. Plug down at 10:50 A. M. July 9, 1972.

RECEIVED
STATE CORPORATION COMMISSION
JUL 13 1972
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Strata Drilling, Inc.

Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.

Charles W. Steincamp (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp

Charles W. Steincamp, President
P. O. Box 355, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of July, 19 72

Elaine H. Taylor
Notary Public.

My commission expires December 14, 1973

ELAINE H. TAYLOR NOTARY PUBLIC BARTON COUNTY, KANSAS

15-135-20635-0000

D R I L L E R S L O G

#1 Miner "I"

CASING RECORD:
335.59' of used 8-5/8" surface casing.

TOTAL DEPTH:
4528'

COMPANY: Thunderbird Drilling, Inc.

CONTRACTOR: Strata Drilling, Inc.

COMMENCED: June 26, 1972

COMPLETED: July 9, 1972

D. & A.

DESCRIPTION: NW NE NW Section 21-17S-26W Ness County, Kansas

ELEVATION: 2536' KB

FORMATION	FROM	TO
Clay, Rock, Shale & Sand	0	365
Shale w/Sand Streaks	365	629
Shale, Red Bed, Sand & Shale	629	1318
#1 Anhydrite	1318	1335
Red Bed	1335	1370
Shale, Red Bed & Dakota Sand	1370	1885
Red Bed, Shale & Shells	1885	1921
#2 Anhydrite	1921	1956
Shale & Shells	1956	2131
Shells, Shale w/Broken Lime	2131	2435
Shale & Lime	2435	3867
Lime	3967	4300
Lime & Shale	4300	4470
Lime, Shale & Chert	4470	4502
Lime	4502	4528

ROTARY TOTAL DEPTH 4528'

REMARKS

Ran 335.59' of used 8-5/8" surface casing; set and cemented at 341.59' with 170 sacks of common cement, 2% gel and 3% C. C. Plug down at 11:00 P. M. June 26, 1972.

RECEIVED
STATE CORPORATION COMMISSION
JUL 13 1972
CONSERVATION DIVISION
Wichita, Kansas

D. & A.

Plugged hole as follows: Plugged at 720' with 70 sacks of regular cement; plugged at 300' with 20 sacks of regular cement; plugged at 40' with 10 sacks of regular cement. Plug down at 10:50 A. M. July 9, 1972.

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp

Charles W. Steincamp, President

Subscribed and sworn to before me this 10th day of July, 1972.

ELAINE H. TAYLOR NOTARY PUBLIC BARTON COUNTY, KANSAS

Elaine H. Taylor

Elaine H. Taylor, Notary Public

My Commission Expires:
December 14, 1973