

15-135-2112-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

_____ Mess _____ County, Sec. 22 Twp. 17B Rge. _____ (E) 26 (W)

Location as "NE/CNWSW" or footage from lines _____
C/SW SW
Lease Owner Strata Drilling Company
Lease Name Scroggins Well No. 1
Office Address P. O. Box 355, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 31 1975
Application for plugging filed October 31 1975
Application for plugging approved October 31 1975
Plugging commenced October 31 1975
Plugging completed October 31 1975
Reason for abandonment of well or producing formation Dry Hole

Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4464 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	281'			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole plugged as follows: Plugged at 950' with 70 sacks of 50-50 pozmix and 2 1/2 gal; plugged at 270' with 20 sacks of 50-50 pozmix and 2 1/2 gal; plugged at 40' with 10 sacks of 50-50 pozmix and 2 1/2 gal. Plug down at 4:00 P. M. October 31, 1975.

RECEIVED
STATE CORPORATION COMMISSION
NOV 5 1975
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Strata Drilling Company
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.

Kenneth J. Link (employee or owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Witness) Kenneth J. Link
Kenneth J. Link, President
P. O. Box 355, Great Bend, Kansas 67530
(Address)

Subscribed and sworn to before me this 5th day of November, 19 75
Elaine H. Taylor
Elaine H. Taylor Notary Public.



D R I L L E R S L O G

#1 Scroggins

CASING RECORD:
275.62' of used 8-5/8"
surface casing.

COMPANY: Strata Drilling Company
CONTRACTOR: Strata Drilling Company

DESCRIPTION: C/SW SW
Section 22-17S-26W
Ness County, Kansas

TOTAL DEPTH:
4464'

COMMENCED: October 23, 1975
COMPLETED: October 31, 1975

ELEVATION: 2496' D.F.
 2499' K.B.

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>	
Surface Soil, Shale & Post Rock	0	300	Ran 275.62' of used 8-5/8" surface casing; set and cemented at 281' with 185 sacks of common cement, 2% gel and 3% C. C. Plug down at 10:45 P. M. October 23, 1975.	
Shale	300	1253		
Anhydrite	1253	1265		
Shale & Red Bed	1265	1340		
Sand	1340	1490		
Sand & Shale	1490	2000		
Shale w/Lime Streaks	2000	2375		
Lime & Shale	2375	3915		
Lime	3915	4050		Ran Drill Stem Test.
Lime & Shale	4050	4240		
Lime	4240	4305		
Lime & Shale	4305	4464		

ROTARY TOTAL DEPTH: 4464'

D. & A.

Hole plugged as follows: Plugged at 950' with 70 sacks of 50-50 pozmix and 2% gel; plugged at 270' with 20 sacks of 50-50 pozmix and 2% gel; plugged at 40' with 10 sacks of 50-50 pozmix and 2% gel. Plug down at 4:00 P. M. October 31, 1975.

NOV 5 1975

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.


STRATA DRILLING COMPANY

Kenneth J. Link
Kenneth J. Link, President

Subscribed and sworn to before me this 5th day of November, 1975.

My Commission Expires:

December 14, 1977



Elaine H. Taylor
Elaine H. Taylor, Notary Public