


15-135-20734-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Ness County. Sec. 23 Twp. 17 Rge. 26 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NE SE
Lease Owner Beardmore Oil, Inc.
Lease Name Norton Well No. 1
Office Address 700 One Twenty Bldg. Wichita, Kans. 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 4/26 19 73
Application for plugging filed 19
Application for plugging approved 19
Plugging commenced 5/29 19 73
Plugging completed 6/1 19 73
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 4424 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	303'	0
				5 1/2"	4411'	3336'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Set plug at 4380'. Run 5 sacks of cement from 4380' to 4350'.

Pumped in 8 5/8" pipe-25 sacks of gel mud, 5 sacks of hulls, 70 sacks of cement, 10 sacks of gel mud, 1-8 5/8" plug & 50 sacks of cement to plug well.

RECEIVED
STATE CORPORATION COMMISSION
JUN 26 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Glenn's Pipe Pulling Co.
Address Box 156 Ellinwood, Kans. 67526

STATE OF Kansas, COUNTY OF Barton, ss.

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Ralph Glenn
Box 156, Ellinwood, Kans.
(Address)

Subscribed and Sworn to before me this 19th day of June, 1973

Carlena Jones
Notary Public.



K-135-20734-0000

WELL LOG

COMPANY Beardmore Oil Inc.

SEC. 23 T. 17S W. 26W
LOC. NE SE

FARM Norton NO. 1

RID. NO. 1

TOTAL DEPTH 4424'

COMM. 4-14-73

COMP. 4-26-73

COUNTY Ness
KANSAS

CONTRACTOR Rains & Williamson Oil Co., Inc.



CASING

10 10
15 8-5/8" @ 303' w/175 sx. 2% gel.
12 4
13 5-1/2" @ 4411' w/175 sx.

ELEVATION

PRODUCTION Oil

FIGURES INDICATE BOTTOM OF FORMATIONS

Post Rock	45
Shale	305
Shale & Sand	975
Shale w/Sand Streaks	1330
Sand	1535
Redbed & Shale	1655
Redbed	1815
Anhydrite	1853
Shale w/Lime Streaks	2160
Shale & Lime	2455
Lime & Shale	3005
Shale & Lime	3195
Lime & Shale	3355
Shale & Lime	3540
Lime & Shale	3655
Lime	4424
<u>RTD</u>	<u>4424</u>

RECEIVED
STATE CORPORATION COMMISSION

JUN 1 1973

CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
County of Sedgwick }

Wilson Rains, President of the Rains & Williamson Oil Company Inc.

upon oath state that the above and foregoing is a true and correct copy of the log of the Norton #1 well.



Subscribed and sworn to before me this 27th day of April
My Commission Expires: October 4, 1975

Wilson Rains
Wilson Rains
19 73
Juanita M. Green
NOTARY PUBLIC
Juanita M. Green