
15-135-21573-0000

FORM CP-4

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above Section Plat

Ness County. Sec. 23 Twp. 17S Rge. 26W E/W
Location as "NE/CNW¼SW¼" or footage from lines
NE SW NE
Lease Owner Palomino Petroleum
Lease Name Norton D Well No. #1
Office Address 500 Insurance Building, Wichita, Kansas 67202
Character of Well (Completed as Oil, Gas or Dry Hole)
dry hole
Date Well completed January 24, 1979 19
Application for plugging filed January 24, 1979 19
Application for plugging approved January 24, 1979 19
Plugging commenced January 24, 1979 19
Plugging completed January 24, 1979 19
Reason for abandonment of well or producing formation
dry hole
If a producing well is abandoned, date of last production
19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey
Producing formation Depth to top Bottom Total Depth of Well 4452'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS — CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set. Hole plugged with 50-50 pozmix, 6% gel, as follows: 70 sacks @ 600', 20 Sacks @ 240', Hulls and 10 sacks @ 40', 5 sacks in rathole. Plugging completed 2:30 p.m., January 24, 1979.

RECEIVED
STATE CORPORATION COMMISSION
FEB 16 1979
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Strata Drilling Company

STATE OF KANSAS COUNTY OF BARTON, ss.
CHARLES W. STEINCAMP (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp
P. O. Box 355, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 1st day of February, 19 79.

Loneita Barry
Loneita Barry Notary Public.

My commission expires 3-28-80.

LONEITA BARRY NOTARY PUBLIC STATE OF KANSAS

15-135-21573-0000

D R I L L E R S L O G

#1 Norton D

CASING RECORD:
8 jts. new 20# 8-5/8" surface casing

TOTAL ROTARY DEPTH: 4452'

COMPANY: Palomino Petroleum

CONTRACTOR: Strata Drilling Company

COMMENCED: January 15, 1979

COMPLETED: January 24, 1979

D & A

DESCRIPTION: NE SW NE Section 23-17S-26W

FORMATION	FROM	TO	REMARKS
Surface soil, shale	0	335	Ran 318' new 20# 8-5/8" surface casing; set and cemented at 323' with 190 sacks common, 2% gel, 3% C.C. Cement circulated. Plug down 8:00 a.m., January 16, 1979.
Shale and shells	335	1035	
Shale	1035	1820	
Anhydrite	1820	1855	
Shale	1855	2295	
Lime and shale	2295	4320	Ran 1 electric log.
Lime	4320	4400	
Lime and shale	4400	4452	Ran 1 Drill Stem Test.
			Hole plugged with 50-50 pozmix, 6% gel, as follows: 70 sacks @ 600', 20 sacks @ 240', hulls and 10 sacks @ 40', 5 sacks in rathole. Plugging completed at 2:30 p.m., January 24, 1979.

RECEIVED
STATE CORPORATION COMMISSION
FEB 16 1979
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) ss
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

Charles W. Steincamp

Charles W. Steincamp

Sworn to and subscribed before me this 1st day of February, 1979.

My appointment expires 3-28-80.

Loneita Barry

Loneita Barry, Notary Public