

API NUMBER 15-135-23917-0000

LEASE NAME Bauer Trust "J"

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

WELL NUMBER 4

4950 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 23 TWP. 17S RGE. 26 (X or W)

LEASE OPERATOR Pickrell Drilling Company, Inc.

COUNTY Ness

ADDRESS 110 N. Market, Suite 205 Wichita, KS 67202

Date Well Completed 02-12-96

PHONE# (316) 262-8427 OPERATORS LICENSE NO. 5123

Plugging Commenced 07-16-98

Character of Well Oil

Plugging Completed 07-16-98

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 07-16-98 (date)

by Mike Maier (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Miss. Depth to Top 4440 Bottom 4455 T.D. 4455

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
		0	225	8 5/8	225	None
		0	4453	4 1/2	4453	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Thru tubing spotted 15 sx 60/40 Poz at 4437. Pulled tubing to 1830 and mixed and pumped 105 sx. 60/40 Poz. Cement circulated. Pulled tubing and filled hole w/ 10 sx 60/40 Poz. Tied into 8 5/8 x 4 1/2 annulus. Used 10 sx. 60/40 Poz to fill and shut in w/ 500#. (See copy of field report attached.)

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied Cementing Co., Inc. License No. _____

Address P.O. Box 628, Great Bend, KS 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Pickrell Drilling Company, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.


Jack Gurley

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Jack Gurley

(Address) Jack Gurley
110 N. Market, #205 Wichita, KS 67202

AND SWORN TO before me this 20th day of August, 19 98



Karen A. Mans McGee
 Notary Public

