

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER 15-135-23,551-00-00

LEASE NAME NORTON "KS"

WELL NUMBER #1

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

4620 Ft. from S Section Line

4290 Ft. from E Section Line

SEC. 23 TWP. 27S RGE. 26 (X) or (W)

COUNTY NESS

LEASE OPERATOR VESS OIL CORPORATION

ADDRESS 8100 E. 22nd North, Bldg. 300 Wichita, KS. 67226

Date Well Completed 3-01-91

PHONE#(316) 686-1537 OPERATORS LICENSE NO. 5030

Plugging Commenced 3-01-91

Character of Well D&A

Plugging Completed 3-01-91

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on March 1, 1991 (date)

by Case Morris (KCC District Agent's Name).

Is ACO-1 filed? to be filed by operator If not, is well log attached? yes

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom \_\_\_\_\_ T.D. 4474'

Show depth and thickness of all water, oil and gas formations.

RECEIVED

OIL, GAS OR WATER RECORDS

CASING RECORD

STATE CORPORATION COMMISSION

| Formation | Content | From | To   | Size   | Put In | Pulled out |
|-----------|---------|------|------|--------|--------|------------|
| surface   |         | 0    | 285' | 8 5/8" | 285'   | none       |
|           |         |      |      |        |        |            |
|           |         |      |      |        |        |            |
|           |         |      |      |        |        |            |

MAR 11 1991

CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

50 sx. @ 1900', 50 sx. @ 1100', 40 sx. @ 650', 50 sx. @ 320', 10 sx. @ 40', 10 sx. in rathole  
Total 215 sx. 60/40 Pozmix, 67 Gal 1/4# floccal per sack

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor L. D. Drilling, Inc. License No. 6039

Address R.R. 1 Box 183 B Great Bend, KS. 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Vess Oil Corporation

STATE OF Kansas COUNTY OF Barton, ss.


L. D. Davis (Employee of Operator) or (~~Owner~~) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) L. D. Davis

L. D. Davis

(Address) R.R. 1 Box 183 B Great Bend KS

SUBSCRIBED AND SWORN TO before me this 7th day of March, 19 91



Bessie M. Dewerff  
Notary Public

Bessie M. Dewerff

My Commission Expires: 5-20-93

DRILLER'S WELL LOG

DATE COMMENCED: 2-21-91

DATE COMPLETED: 3-01-91

0 - 285 Shale & clay  
 285 - 1858 Shale  
 1858 - 1888 Anhy  
 1888 - 2555 Shale & lime  
 2555 - 2775 Lime & Shale  
 2775 - 2955 Shale & Lime  
 2955 - 3330 Lime & Shale  
 3330 - 3504 Shale & Lime  
 3504 - 3880 Lime & Shale  
 3880 - 4030 Shale & Lime  
 4030 - 4272 Lime  
 4272 - 4350 Shale & Lime  
 4350 - 4474 Lime  
 4474 RTD

VESS OIL CORPORATION  
 Norton "KS" #1  
 E/2 NW NW  
 Sec. 23, T17S, R26W  
 Ness County, KS.

ELEVATION: 2503 GL 2508 KB

SURFACE PIPE:

8 5/8" set @ 285' W/165 sx.  
 60/40 pozmix, 2% Gel, 3% CC


AFFIDAVIT

STATE OF KANSAS )  
 COUNTY OF BARTON) <sup>ss</sup>

L. D. Davis of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.

L. D. Davis  
 L. D. Davis

Subscribed and sworn to before me this 7th day of March 1991.



Bessie M. DeWerff  
 Notary Public  
 Bessie M. DeWerff

RECEIVED  
 STATE CORPORATION COMMISSION

MAR 11 1991

CONSERVATION DIVISION  
 Wichita, Kansas