


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

15-135-0004-0000
WELL PLUGGING RECORD



Locate well correctly on above Section Plat

Ness County, Sec. 28 Twp. 17 Rge. 26W (E) (W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines NW NW SE
Lease Owner Rycade Oil Corporation
Lease Name Solze Well No. 1
Office Address Esperson Building, Houston, Texas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 22, 1951 (rotary tools) 19
Application for plugging filed December 13, 1951 (verbal) 19
Application for plugging approved December 13, 1951 (verbal) 19
Plugging commenced December 13, 1951 19
Plugging completed December 23, 1951 19
Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production none 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough, Great Bend, Kans.
Producing formation Depth to top Bottom Total Depth of Well 4433 Feet
Show depth and thickness of all water, oil and gas formations.


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8-5/8"	172'	
				5-1/2"	4401'	4325'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

172 feet of 8-5/8" surface pipe circulated with cement. 5-1/2 inch casing set at 4421 feet cemented with 50 sacks. Plugged back to 4325 feet with chat. Dumped 5 sacks of cement at 4325 feet; shot off and pulled the 5-1/2 inch casing. Mud to 175 feet; set rock bridge and 20 sacks of cement at 175 feet. Mud to 35 feet; plug and 10 sacks of cement at the surface.



(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor R. S. Pipe Pulling Company
Address Ellinwood, Kansas

STATE OF Texas, COUNTY OF Harris, ss.
W. T. Harris, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) W. T. Harris, Jr.
Esperson Building, Houston 2, Texas (Address)

SUBSCRIBED AND SWORN to before me this 14th day of January, 1952.
Bessie New Notary Public.

My commission expires June 1, 1953 23-8390-s 6-51-20M

PLUGGING
FILE SEC 28 T 17 R 26
BOOK PAGE 134 LINE 11

15-135-00040-0000

CERTIFIED DRILLER'S LOG

Lease: Solze #1

Company: Rycade Oil Corporation and Federal Royalty Company

Contractor: H & H Drilling Company

Location: NW NW SE
28-17S-26W
Ness County

Commenced: 10-2-51

Completed: 10-22-51 (Rotary tools)

Casing Record:
172' 8-5/8" cem. w/125
4404' 5-1/2" cem. w/50

Elevation: 2463 d.f.

FORMATION	DEPTH	REMARKS
Clay	0-20	
Post Rock	20-60	
Sand	60-80	
Shale (blue)	80-337	
Sand & Shale	337-398	
Shale	398-665	
Sand	665-750	
Shale & Shell	750-1000	
Red Bed	1000-1160	
Shale	1160-1230	
Anhydrite	1230-1244	
Shale & Shell	1244-1835	
Shale	1835-2105	
Shale w/Lime	2105-2220	
Shale	2220-2365	
Shale & Lime	2365-2440	
Shale	2440-2560	
Shale & Shell	2560-2820	
Lime	2820-2852	
Lime & Shale	2852-2965	
Shale & Lime	2965-3211	
Lime w/Shale	3211-3291	
Lime & Shale	3291-3404	
Lime w/Shale	3404-3472	
Lime	3472-4220	
Lime & Shale	4220-4303	
Lime w/Shale	4303-4333	
Lime & Shale	4333-4407	
Total Depth	4407	

I hereby certify that this is a true and correct copy of the above log, to the best of my knowledge.

W. L. Hartman

STATE OF KANSAS)
COUNTY OF SEDGWICK)

SUBSCRIBED AND SWORN TO before me this 24th day of October 1951.

George L. Land
Notary Public

My Commission Expires: May 13, 1953

RECEIVED
OCT 26 1951
DIVISION

FILE 28 17 Row
PAGE 134