

15-135-00146-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Ness County. Sec. 28 Twp. 17 Rge. 26 ~~(D)~~ (W)

Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C NE NE  
Lease Owner W. L. Hartman  
Lease Name Scott-Solze Well No. 1  
Office Address P. O. Box 54, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed 1-7-52 19  
Application for plugging filed November 21, 1951 19  
Application for plugging approved November 23, 1951 19  
Plugging commenced December 23, 1951 19  
Plugging completed January 7, 1952 19  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough  
Producing formation Depth to top Bottom Total Depth of Well 4516 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				13-3/8"	120'	
				5-1/2"	4436'	1906'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

4325 to 4300 ft.	Sand bridge.
4300 to 4270 ft.	5 sks. cement
4270 to 140 ft.	Mudded
140 to 130 ft.	Rock bridge
130 to 100 ft.	30 sax cement
100 to 12 ft.	Mud
12 ft. to cellar	10 sax cement

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to W. L. Hartman  
Address P. O. Box 54  
Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
W. L. Hartman (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *W. L. Hartman*  
P. O. Box 54, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 16th day of January, 1952

*Georgia L. Lard* Notary Public.

My commission expires May 13, 1953

23-3273-s 4-50-10M

PLUGGING  
FILE SEC 28 T 17 R 26  
BOOK PAGE 185 LINE 44

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 18 1952  
CONSERVATION DIVISION  
Wichita, Kansas

Company: W. L. Hartman  
Contractor: H & H Drilling Co.  
Commenced: 6-17-50  
Completed: 7-3-50 (Rotary tools)  
Elevation: 2487 D.F.

Lease: Scott-Solze #1  
Location: C NE NE 28-17-26W  
Ness County, Kansas

Casing Record:  
120' 13-3/8" cem. W/75 sax.  
4436 1/2' 5-1/2" cem. W/50 sax.

CERTIFIED DRILLERS LOG

Formation	Depth	Remarks
Clay	0-30	
Sand	30-50	
Shale	50-120	
Blue Shale	120-580	
Red Bed	580-690	
Sand	690-750	
Shale & Shell	750-1165	
Shale	1165-1240	
Anhydrite	1240-1270	
Shale	1270-1300	
Red sand and Shale	1300-1737	
Shale & Shell	1737-1846	
Lime	1846-1956	
Lime & Shale	1956-2020	
Shale	2020-2130	
Shale	2130-2355	
Lime	2355-2368	
Shale	2368-2658	
Shale & Shell	2658-2700	
Lime & Shale	2700-2757	
Lime	2757-3269	
Lime & Shale	3269-3676	
Shale	3676-3677	
Lime	3677-3695	
Shale & Lime	3695-3746	
Lime	3746-3782	
Shale & Lime	3782-3821	
Lime	3821-3825	
Chert	3825-3858	
Lime	3858-4093	
Lime & Shale	4093-4130	
Lime	4130-4140	
Shale	4140-4160	
Lime & Shale	4160-4305	
Shale	4305-4336	
Shale & Lime	4336-4417	
Lime & Shale & Cherty Lime	4417-4424	
Lime	4424-4516	
Total Depth	4516	

DERRICK FLOOR TOPS

Stone Corral	1848
Topska	3502
Lansing	3851
Marmaton "Lime"	4332
Conglomerate	4401
Conglomerate (Chert)	4416
Mississippi	4436
Total Depth	4514

I hereby certify that this is a true and correct copy of the above log, to the best of my knowledge.

*W. L. Hartman*

STATE OF KANSAS )  
COUNTY OF SEDGWICK)

Subscribed and sworn to before me this 12th day of July 1950.

*Georgia L. Laird*  
Notary Public

My Commission expires May 13, 1953

PLUGGING  
FILE SEC 28-17-R-260  
BOOK PAGE 125 LINE 44

STATE OF KANSAS  
JAN 18 1952  
COMMISSION EXPIRES  
KANSAS