

15-135-00108-0000

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NESS

County. Sec. 29 Twp. 17 Rge. 26 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NE, SW, SW

Lease Owner MULL DRILLING COMPANY

Lease Name SHUMATE Well No. 1

Office Address 670 FOURTH NATIONAL BLDG., WICHITA, KANSAS

Character of Well (completed as Oil, Gas or Dry Hole) DRY ROTARY

Date well completed 9-13 19 58

Application for plugging filed 9-13 19 58

Application for plugging approved 9-13 19 58

Plugging commenced 9-14 19 58

Plugging completed 9-14 19 58

Reason for abandonment of well or producing formation NO PRODUCTIBLE ZONE

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well GILBERT P. LEIKER

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4576' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8" @	210' W/	150 sax.

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Heavy mud to 600', placed 1/2 sx. hulls, wooden plug and pushed to 600', capped with 20 sx. cement through drill pipe.
Heavy mud to 200', placed 1/2 sx. hulls, wooden plug and pushed to 200', capped with 20 sx. cement through drill pipe.
Heavy mud to 40', 1/2 sx. hulls, wooden plug, pushed plug to 20', capped with 10 sx. cement to base of well cellar.
Job complete @ 4:15 AM, 9-14-58

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GARVEY DRILLING COMPANY
Address ROUTE #2, GREAT BEND, KANSAS

STATE OF KANSAS, COUNTY OF BARTON, ss.
VERNE A. MORRIS

(employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Verne A. Morris

September 16, 1958

(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of September, 19 58

My commission expires November 12, 1958

Notary Public.

RECEIVED
SEP 19 1958
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 29 T 17 R 26 W
BOOK PAGE 130 LINE 25

WELL LOG

15-135-00108-0000

COMPANY **MULL DRILLING COMPANY**

SEC. **29 T. 17S R. 26W**

FARM **SHUMATE**

NO. **1**

LOC. **NE, SW, SW**


TOTAL DEPTH **4576'**

COUNTY **NESS CO., KANSAS**

COMM. **September 2, 1958**

COMP. **September 14, 1958**

CONTRACTOR **GARVEY DRILLING COMPANY**



CASING **8 5/8" @ 210' W/150 sax.**

ELEVATION **2577' DF**

PRODUCTION **D & A**

FIGURES INDICATE BOTTOM OF FORMATIONS

130	Sand & shale
1046	Shale & sand
1090	Anhydrite
2865	Shale & shells
2960	Lime
3460	Lime & shale
3760	Shale & lime
3887	Lime & shale
4430	Lime
4477	Lime & shale
4558	Lime
4576	Chert & lime
4576	T. D.

RECEIVED
 ST. ... COMMISSION
 OCT 2 1958
 C. ... COMMISSION

PLUGGING
 FILE SEC 29 T. 17 R. 26W
 BOOK PAGE 130 LINE 25

State of KANSAS }
 County of BARTON } ss:

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 SHUMATE well

Subscribed and sworn to before me this 24th day of September 19 58

My Commission Expires: November 12, 1958

[Signature]
 NOTARY PUBLIC