


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD



Locate well correctly on above
Section Plat

Ness County. Sec. 27 Twp. 18S Rge. 24W (E) (W)
Location as "NE/CNW/SW" or footage from lines C SE SW
Lease Owner Hellar Drilling Co., Inc. & George Grenyo, et al
Lease Name Miner Well No. 1
Office Address 1014 Union Center Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 30 19 64
Application for plugging filed October 30 19 64
Application for plugging approved October 30 19 64
Plugging commenced October 30 19 64
Plugging completed October 30 19 64
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Elving
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well _____ Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Bottom plug at 245'. 2 sacks dry cement, 1/3 sack hulls, 10 gallons water, 25 sacks cement. Heavy mud to 40'. 2 sacks dry cement, 1/3 sack hulls, 10 gallons water, plug 10 sacks cement.

RECEIVED
STATE CORPORATION COMMISSION

NOV 9 1964

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Hellar Drilling Co., Inc.
Address 1014 Union Center Building, Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
D. L. Hellar (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) D. L. Hellar
D. L. Hellar, President
1014 Union Center Building, Wichita, Ks. (Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of November, 19 64

My commission expires June 18, 1968
Minnie E. Matson
Minnie E. Matson Notary Public.

DRILLER'S LOG

COMPANY: Hellar Drilling Co., Inc. & George Grenyo, etal
 CONTRACTOR: Hellar Drilling Company, Inc.
 LEASE: #1 Miner
 LOCATION: C SE SW of Section 27-18S-24W,
 Ness County, Kansas'
 COMMENCED: October 19, 1964
 COMPLETED: October 29, 1964
 CASING: 8-5/8" set at 248' with 200 sacks cement.

0 - 249	Shale Blue
249 - 945	Sand and Shells
945 - 951	Anhydrite
951 - 1459	Sand, Shells and Red Bed
1459 - 1562	Shale and Shells
1562 - 1600	Anhydrite
1600 - 1755	Shale and Shells
1755 - 1995	Salt Section
1995 - 2175	Shale
2175 - 2372	Ft. Riley Lime and Chert
2372 - 2545	Lime and Shale
2545 - 2635	Lime
2635 - 3325	Lime and Shale
3325 - 3532	Shale, Lime and Chalk
3532 - 3717	Lime and Shale
3717 - 3885	Kansas City Lime
3885 - 4005	Lime
4005 - 4078	Lime and Shale
4078 - 4105	Lime
4105 - 4165	Lime and Shale
4165 - 4242	Lime and Streaks of Shale
4242 - 4295	Lime and Shale
4295 - 4344	Lime and Dolomite
4345	Rotary Total Depth

RECEIVED
 STATE CORPORATION COMMISSION


NOV 9 1964

CONSERVATION DIVISION
 Wichita, Kansas

STATE OF KANSAS)
) SS.
 COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Miner, located in the C SE SW of Section 27-18S-24W, Ness County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.



 President - D. L. Hellar

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 3rd day of November, 1964.



 Notary Public - Minnie E. Matson

My commission expires 6-18-68.