

15-135-20722-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027
Wichita, Kansas 67217
NORTH



Locate well correctly on above
Section Plat

Ness County. Sec. 27 Twp. 18S Rge. (E) 24(W)
Location as "NE/CNW/SW" or footage from lines C/NW NE
Lease Owner Thunderbird Drilling, Inc.
Lease Name Stopple Well No. 1
Office Address 4328 East Kellogg, P. O. Box 18407, Wichita, Kansas 67218
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed January 13 19 73
Application for plugging filed January 13 19 73
Application for plugging approved January 13 19 73
Plugging commenced January 13 19 73
Plugging completed January 13 19 73
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4331 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	8-5/8"	0	351.61'			


Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.
Plugged hole as follows: Plugged at 600' with 70 sacks of 50-50 pozmix & 6% gel; plugged at 300' with 20 sacks of 50-50 pozmix & 6% gel; plugged at 40' with 10 sacks of 50-50 pozmix & 6% gel. Plug down at 11:00 A. M. January 13, 1973.

RECEIVED
STATE CORPORATION COMMISSION
JAN 23 1973
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Strata Drilling, Inc.
Address P. O. Box 355, Great Bend, Kansas 67530

STATE OF KANSAS COUNTY OF BARTON ss.
Charles W. Steincamp (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles W. Steincamp
Charles W. Steincamp, President
P. O. Box 355, Great Bend, Kansas 67530
(Address)



Subscribed and sworn to before me this 18th day of January, 19 73
My commission expires December 14, 1973
Elaine H. Taylor Notary Public.

15-135-20722-0000

DRILLERS LOG

#1 Stopple

CASING RECORD:
345.61' of used 8-5/8"
surface casing.

COMPANY: Thunderbird Drilling, Inc.
CONTRACTOR: Strata Drilling, Inc.

DESCRIPTION: C/NW NE
Section 27-18S-24W
Ness County, Kansas

TOTAL DEPTH:
4331'

COMMENCED: January 1, 1973
COMPLETED: January 13, 1973

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Clay & Shale	0	364	Ran 345.61' of used 8-5/8" surface casing; set and cemented at 351.61' with 195 sacks of common cement, 2% gel and 3% C. C. Plug down at 8:55 P. M. January 2, 1973.
Shale, Sand, Red Bed	364	610	
Shale	610	917	
Anhydrite	917	927	
Shale, Shells	927	992	
Sand	992	1240	
Shale w/Sand Streaks	1240	1538	
Anhydrite	1538	1583	
Shale	1583	1832	
Sand Streaks, Shells & Shale	1832	2216	
Shale w/Lime Streaks	2216	2638	
Lime & Shale	2638	4158	
Lime	4158	4277	
Lime & Shale	4277	4300	
Lime	4300	4331	

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 23 1973
 CONSERVATION DIVISION
 Wichita, Kansas

Ran electric log.

ROTARY TOTAL DEPTH: 4331'

D. & A.

Plugged hole as follows: Plugged at 600' with 70 sacks of 50-50 pozmix & 6% gel; plugged at 300' with 20 sacks of 50-50 pozmix & 6% gel; plugged at 40' with 10 sacks of 50-50 pozmix & 6% gel. Plug down at 11:00 A. M. January 13, 1973.

STATE OF KANSAS)
) ss.
COUNTY OF BARTON)

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING, INC.

Charles W. Steincamp
Charles W. Steincamp, President

Subscribed and sworn to before me this 18th day of January, 1973.

My Commission Expires:
December 14, 1973

Elaine H. Taylor
Elaine H. Taylor, Notary Public