


15-135-21350-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Commission
245 North Water
Wichita, KS 67202

FORM CP-4

WELL PLUGGING RECORD



Locate well correctly on above
Section Plot

Ness County. Sec. 22 Twp. 18 Rge. 24 (E) W(W)
Location as "NE/CN\WKS\W" or footage from lines 150' S. of C. SE. NW
Lease Owner Vincent Oil Corporation
Lease Name Gabel No. 1 Well No. 1
Office Address 901 Union Center Building, Wichita 67202
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 8/7/77 19
Application for plugging filed 8/7/77 19
Application for plugging approved 8/7/77 19
Plugging commenced 8/7/77 19
Plugging completed 8/7/77 19
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Leo F. Massey
Producing formation Depth to top Bottom Total Depth of Well 4326 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface	0	312'	8-5/8	yes	no

RECEIVED
STATE CORPORATION COMMISSION

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

CONSERVATION DIVISION
Wichita, Kansas

Bottom plug at 550' with 70 sacks 50/50 poz, 2% gel
Second plug at 240' with 25 sacks 50/50 Poz, 2% gel
Top & bridge at 40' with 10 sacks 50/50 Poz, 2% gel
2 sacks in rathole
Job complete at 11:45 a.m. 8/7/77

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Slawson Drilling Company, Inc.
Address 200 Douglas Building, Wichita, Kansas 67202


STATE OF Kansas COUNTY OF Sedgwick ss.
James C. Remsberg (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) James C. Remsberg
200 Douglas Building, Wichita, Kansas
(Address)

Subscribed and sworn to before me this 15 day of August 1977

Mary Lou Taylor
Mary Lou Taylor Notary Public

My commission expires January 17, 1981



15-135-21350-0000

DRILLERS LOG

OPERATOR: Vincent Oil Corporation
 901 Union Center Building
 Wichita, Kansas 67202

LEASE: Gabel No.1
 150' S of C SE NW
 Sec. 22-18S-24W
 Ness County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
 200 Douglas Building
 Wichita, Kansas 67202

COMMENCED: 7-30-77

COMPLETED: 8-7-77

RTD: 4326'

CASING: Used 8-5/8" set at 312' with 225 sax cement

RECEIVED
STATE CORPORATION COMMISSION

AUG 16 1977

CONSERVATION DIVISION
Wichita, Kansas

0' to 316' 12 1/2" surface hole (Shale)
 316' to 1408' Sand-Shells
 1408' to 1555' Shells
 1555' to 1598' Anhydrite
 1598' to 1835' Shale
 1835' to 2410' Shale & Lime
 2410' to 2860' Lime & Shale
 2860' to 3097' Shale & Lime
 3097' to 3225' Lime & Shale
 3225' to 3555' Shale & Lime
 3555' to 4187' Lime & Shale
 4187' to 4215' Lime
 4215' to 4220' Lime & Shale
 4220' to 4300' Lime
 4300' to 4326' Lime & Shale
 4326' RTD

State of Kansas

County of Sedgwick

I, James C. Remsberg, of the Slawson Drilling Company, Inc. hereby state that the above and foregoing is a true and accurate copy of the log of the No. 1 Gabel.

James C. Remsberg

Subscribed and sworn to me this 15th day of August, 1977

Mary Lou Taylor
Mary Lou Taylor, Notary

My commission expires January 17, 1981

