

15-135-20037-00-00

Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JUN 23 1967
06-23-1967
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name Pickrell Drlg Co

Complete Address: 705 S 4th Natl Bank Bldg. Wichita, Kansas

Lease Name WEGELE Well No. B 1

Location C NW SE Sec. 21 Twp. 18 Rge. 22 (E) (W)

County Ness Total Depth 4446

Abandoned Oil Well Gas Well Input Well SWD Well D & A x

Other well as hereafter indicated:

Plugging Contractor: Co Tools

Address: License No.

Operation Completed: Hour 12 p Day 19 Month June Year 1967

The Above well was plugged as follows:

Total Depth 4446 8 5/8 set at 165

Gunned pits circulated hole with heavy mud, set cementing plug at 540 ft.,
and displaced 20 sack cement thru drill pipe, heavy mud to 300 ft., set
cementing plug and displaced 25 sack cement thru drill pipe, heavy mud to 40 ft.,
set cementing plug, 3 sack hulls and 10 sack cement, cementing to base of collar.
Cementing by Globe Cementing Co

I hereby certify that the above well was plugged as herein stated Gilbert B. Leiker

INVOICED

Signed: Gilbert B. Leiker
Well Plugging Supervisor

DATE 6/27/67
INV. NO. 5463-W