

R

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

Form CP-3

RECEIVED
STATE CORPORATION COMMISSION
6-28-68

JUL 11 1977
07-11-1977
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 135 - 21087 - 00-00 (of this well)

Operator's Full Name Petroleum, Inc.

Complete Address Box 1447, Great Bend, Kansas 67530

Lease Name Somy Well No. 1

Location C NW SW Sec. 5 Twp. 17 Rge. (E) (W) 24

County Ness Total Depth 4532

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Pipe Pullers, Inc.

Address Box 486, Ellinwood, Kansas 67526 License No. 462

Operation Completed: Hour 12 :15 P Day 8 Month 7 Year 1977

The above well was plugged as follows:

Total Depth 4532' 8 5/8 csg set 287' cwc 185 sk.

5 1/2 csg set 4531' ow 85 sk cem.

5 1/2 csg PBSD 4439' with top perf. (4402')

Filled 5 1/2 csg with sand (4439'-4390') dumped 4 sk cem W/dump bailer. (4390'-4360')

Cutoff & recovered 3814' of 5 1/2 csg.

Sun Cementing Co. mixed & pumped down 8 5/8 csg with 20 sx gel & water W/200 lbs

hulls, followed with 70 sk 50-50 poz 6% -displaced with 12 sk gel & water & capped

with cementing plug & 80 sk 50-50 poz 6% & shutin. FPP 350 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo Massey
Well Plugging Supervisor

DATE 7-12-77

INV NO. 5459-w