

15-135-21318-0000

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAY 09 1977  
05-09-1977  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 135- 21,318 (of this well)

Operator's Full Name Liberty Enterprises, Inc.

Complete Address 308 W. Mill, Plainville, Kansas 67663

Lease Name Seltman Well No. 1

Location SW NW Sec. 5 Twp. 17 Rge. (E) (W) 24

County Ness Total Depth 4519'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor C & G Drlg.

Address Wichita, Kansas License No.       

Operation Completed: Hour 7:30 A Day 6 Month 5 Year 1977

The above well was plugged as follows:

RTD 4519' 8 5/8 csg 279' cwc 160 sx. Flg. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set 70 sk cmt plug at 800' thru drill pipe.

Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud to 40' set solid  
bridge & 10 sk cmt plug to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INDEXED

Signed: [Signature]  
Well Plugging Supervisor

DATE 5-9-77  
NO. 5112-W