

15-135-20577-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 11 1974  
CONSERVATION DIVISION  
Wichita, Kansas  
10-11-1974

Operator's Full Name Omar Oil Company

Complete Address 1130 Vickers KSB&T Bldg., Wichita, Kansas 67202

Lease Name Klitzke Well No. 1

Location W/2 SW SE Sec. 2 Twp. 17 Rge. (E) (W) 24

County Ness Total Depth 4480'

Abandoned Oil Well XX Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor Southwest Casing Pulling

Address Box 364, Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 12 N Day 8 Month 10 Year 1974

The above well was plugged as follows:

Total Depth 4480' 8 5/8 csg set at 283' cwc 180 sk.

5 1/2 csg set at 4468' cw 75 sk cmt.

Filled 5 1/2 csg with sand (4480'-4450') dumped 5 sk cmt W/dump bailer. (4480'-4425')

Cutoff & recovered 2230' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/200 lbs hulls -70 sk 50-50 poz 6% -

10 sk gel & water -released 8 5/8 plug & pumped 50 sk 50-50 poz 6% by Allied.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo J. Massey  
Well Plugging Supervisor

10/11/74  
86-W