

15-135-20185-00-00

Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 23 1968  
CONSERVATION DIVISION  
Wichita, Kansas

09-23-1968

Operator's Full Name Pickrell Drilling Company

Complete Address: 705.4th Nat'l Bk. Bldg. Wichita, Kansas

Lease Name Hall "J" Well No. 1

Location SW SE Sec. 2 Twp. 17 Rge. 24 (E) (W) X

County Ness Total Depth 4500'

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A XX

Other well as hereafter indicated:     

Plugging Contractor: Co. Tools

Address:      License No.     

Operation Completed: Hour 11A Day 20 Month 9 Year 1968

The Above well was plugged as follows:

RTD 4500' 8 5/8 csg set at 244' cwc 185 sc. Cem. Mat. 50-50 poz W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 990' and displaced 70 sc cmt

thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sc cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cmt to base

of cellar. Plugged rat hole with 2 sc cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey  
Well Plugging Supervisor

INVOICED  
DATE 9/23/68  
INV. NO. 8504-W