

15-135-20103-00-00

Form CP-3  
Rev. 6-9-67

KANSAS

*Y*

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

JAN 5 1968

01-05-1968

Operator's Full Name Mack Oil Company

Complete Address 812 Union Center Bldg., Wichita, Kansas

Lease Name Horchem Well No. 2

Location C NW NW Sec. 2 Twp. 17 Rge. 24 (E) (W) X

County Ness Total Depth 4578

Abandoned Oil Well      Gas Well      Input Well      SWD Well      D & A X

Other well as hereafter indicated     

Plugging Contractor      Co. Tools     

Address      License No.     

Operation Completed: Hour 4:15 P Day 3 Month 1 Year 1968

The above well was plugged as follows:

RTD 4578' 8 5/8 csg set at 267' cwc 185 sc. Cementing Material 50-50 Poz W/6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 900' and displaced 100 sc cem.

thru drill pipe. Heavy mud to 270' set cementing plug and displaced 25 sc cement thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base

of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: *L. J. ...*  
Well Plugging Supervisor

INVOICED  
DATE 1/5/68  
INV. NO. 7048-W