

15-135-00013-00-01

Form CP-3  
Rev. 6-26-62

KANSAS

*JP*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 8 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
07-08-1968

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 Fourth National Bldg., Wichita, Kansas

Lease Name HULLOLT (CWO) Well No. 1

Location SW SW NE Sec. 2 Twp. 17 Rge. 24 (E) (W) X

County Ness Total Depth 4595

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A  *(CWO)*

Other well as hereafter indicated: (CWO)

Plugging Contractor: Co. Tools

Address: \_\_\_\_\_ License No. \_\_\_\_\_

Operation Completed: Hour 4:30A Day 1 Month 7 Year 1968

The Above well was plugged as follows:

RTD 4595' 8 5/8 csg at 170' cwc. Cem. Mat. 100 sc 50-50 poz cem. W/6% total gel.  
Gunned pits, circulated heavy mud, set cementing plug at 900' and displaced 70 sc cem.  
thru drill pipe. Heavy mud to 180' set cementing plug displaced 20 sc cement thru drill  
pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base of  
cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: *Leo F. Mussey*  
Well Plugging Supervisor

INVOICED

DATE 7/9/68  
WELL NO. 8068-W