

15-135-20099-0000

Form CP-3
Rev. 6-9-67

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
JAN - 8 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Mull Drilling Company Inc.
Complete Address 1625 Wichita Plaza, Wichita, Kansas
Lease Name Doebbeling Well No. 2
Location C SW NE Sec. 32 Twp. 18 Rge. 24 (E) (W) X
County Ness Total Depth 4441
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated

Plugging Contractor Vaughan Drilling Co.
Address Great Bend, Kansas License No.

Operation Completed: Hour 11 P Day 5 Month 1 Year 1968

The above well was plugged as follows:

RTD. 4441 8 5/8 csg set at 413' cwc 225 sc.

Gunned pits, circulated heavy mud, set cementing plug at 1330' and displaced 100 sc cem.
thru drill pipe. Heavy mud to 420' set cementing plug and displaced 25 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2 sc cement.

I hereby certify that the above well was plugged as herein stated.

Signed: R. F. Muesey
Well Plugging Supervisor

1/8/68
4059-W