



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
OCT 24 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Levic Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name The National Oil Company
Complete Address Suite 550, O. W. Garvey Bldg., Wichita, Kansas
Lease Name Doebbeling Well No. 1
Location C SW NE SW Sec. 32 Twp. 18 Rge. (E) (W) 24
County Ness Total Depth 4434'
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor H-30 Drlg
Address Wichita, Kansas License No.
Operation Completed: Hour 4:45P Day 22 Month 10 Year 1974

The above well was plugged as follows:

RTD 4434' 8 5/8 csg set at 257' cwc 185 sk. Cmt. Mat. 50-50 poz 6% total gel.
Gunned pits, circulated heavy mud, displaced 70 sk cmt plug at 700' thru drill pipe.
Heavy mud to 250' & displaced 20 sk cmt plug thru drill pipe. Heavy mud to 40'
solid bridge & 10 sk cmt to base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo F. Massey
Well Plugging Supervisor

INVOICED

DATE: 10/24/74
IN. 188-W