

15-135-20085-0000

R

KANSAS

Form CP-3
Rev. 6-26-62

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

NOV 28 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Operator's Full Name Mack Oil Company
Complete Address: 812 Union Center Bldg., Wichita, Kansas
Lease Name Korbe Well No. 1
Location C SE SE Sec. 29 Twp. 18 Rge. 24 (E) (W) X
County Ness Total Depth 4392
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated:
Plugging Contractor: Co. Tools

Address: License No.
Operation Completed: Hour 11 A Day 26 Month 11 Year 1967

The Above well was plugged as follows:
RTD 4392' 8 5/8 csg set at 400' cwc 275 sc. Plugging material 50-50 Poz W/6% gel.
Gunned pits, circulated heavy mud; set cementing plug at 720' and displaced 70 sc cem.
thru drill pipe. Heavy mud to 390' set cementing plug and displaced 20 sc cement thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sc hulls and 10 sc cement to base
of cellar. Plugged rat hole with 2, sc cement.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Massey
Well Plugging Supervisor

DATE 11-28-67
INV. NO. 6784-W