

15-135-20301-0000

Form CP-3
Rev. 6-4-68

KANSAS

Y
STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
DEC 3 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Beardmore Drilling, Inc.
Complete Address 700 One Twenty Bldg., Wichita, Kansas
Lease Name Korbe. Well No. 1
Location C SW SE Sec. 29 Twp. 18 Rge. (E) (W) 24
County Ness Total Depth 4396
Abandoned Oil Well Gas Well Input Well SWD Well D & A XX
Other well as hereafter indicated
Plugging Contractor R & W Drlg.
Address Wichita, Kansas License No.
Operation Completed: Hour 8:30P Day 1 Month 12 Year 1969

The above well was plugged as follows:

RTD 4396' 8 5/8 csg set at 427' cwo. Cmt. Mat. 50-50 poz cmt w/6% total gel.
Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 50 sk cmt
thru drill pipe. Heavy mud to 420' set cementing plug and displaced 25 sk cmt thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base
of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo. J. Marsavage
Well Plugging Supervisor

DATE 12/3/69
INV. NO. 970-W