

15-135-20242-00-00

Form CP-3
Rev. 6-26-62

KANSAS

110

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAY 14 1969
CONSERVATION DIVISION
Wichita, Kansas
05-14-1969

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Hill Drilling Co. Inc.

Complete Address: 1625 Wichita Plaza Wichita, Kansas

Lease Name Hildred Schaben Well No. 1

Location SE NW Sec. 19 Twp. 17 Rge. (E) (W) 24

County Ness Total Depth 4370

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: Rains & Williamson

Address: Wichita, Kansas License No.

Operation Completed: Hour 12N Day 12 Month 5 Year 1969

The Above well was plugged as follows:

RTD 4370' 8 5/8 csg set at 248' cwc 160 sk. Cmt. Mat. 50-50 poz cmt. 11/63 total gel.

Gunned pits, circulated heavy mud, set cementing plug at 800' and displaced 70 sk cmt.

thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt thru

drill pipe. Heavy mud to 40' set cementing plug, 1/2hulls and 10 sk cmt to base of cellar

plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Geo F. Massey
Well Plugging Supervisor

DATE 5/14/69
INV. NO. 9740-W