

15-135-20884 00-00

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 2 1974
07-02-1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Zorger Oil Company

Complete Address 706 Union Nat'l Bldg., Wichita, Kansas

Lease Name Noll Well No. 1

Location C NE SW Sec. 15 Twp. 17 Rge. (E) (W) 24

County Ness Total Depth 4545'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor B & B Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 10:30 P. Day 29 Month 6 Year 1974

The above well was plugged as follows:

RTD 4545' 8 5/8 csg set at 354' cwo: 200 sk. Cem. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 bk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Leo Z. Massey
Well Plugging Supervisor

INVOICED

DATE 7/2/74
INV. NO. 9420-W