

15-135-20580-00-00

2

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION

SEP 24 1973
09-24-1973
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Weed Oil Company

Complete Address 800 Thursten National Bldg., Tulsa, Oklahoma 74103

Lease Name Eva Nell Well No. 1

Location C NE NW Sec. 15 Twp. 17 Rge. (E) (W) 24

County Ness Total Depth 4495'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelse Pipe Pulling

Address Bex 176 Chase, Kansas 67524 License No. 683

Operation Completed: Hour 12:30 P Day 22 Month 9 Year 1973

The above well was plugged as follows:

Total Depth 4495' 10 3/4 csg set at 361' cwc

5 1/2 csg set at 4432' cw 150 sk cmt.

5 1/2 csg FBTD 4300' with perf. (4211-4218)

Set 5 1/2 weed plug at 4120' -peured ^{sand} to 4050' -dumped 5 sk cmt W/dump bailer.

Cutoff and recovered 3081' of 5 1/2 csg.

Pumped down 10 3/8 csg with 20 sk gel & water W/500 lbs hulls --70 sk cmt--10 sk gel & water --released 10 3/8 plug and pumped 50 sk cmt.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo J. Maxey
Well Plugging Supervisor

DATE 9-24-73
INV. NO. 7951-02