

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-109-21096-00-00  
Spot: NWSWNWNE Sec/Twnshp/Rge: 14-15S-34W  
726 feet from N Section Line, 2890 feet from W Section Line  
Lease Name: MCDANIEL Well #: 2  
County: LOGAN Total Vertical Depth: 4692 feet

Operator License No.: 33554  
Op Name: K & B NORTON OIL & INVESTMENTS,  
Address: 1209 W. PARK GROVE DR.  
MANHATTAN, KS 66503

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	290		185 sx

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/03/2012 12:00 AM  
Plug Co. License No.: 6039 Plug Co. Name: L. D. DRILLING, INC.  
Proposal Revd. from: RICK Company: L. D. DRILLING, INC. Phone: (620) 617-4794

Proposed Plugging Method: Ordered 205 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: NONE  
Date/Time Plugging Completed: 06/03/2012 6:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

1st plug @2314 w/25 sx  
2nd plug @1121 w/100 sx  
3rd plug @340 w/40 sx  
4th plug @40 w/10 sx  
  
Rathole 30 sx

Perfs:

Remarks: ALLIED

Plugged through: DP

RECEIVED  
JUN 14 2012

KCC WICHITA

District: 04

Signed

Richard Williams  
6/15/12  
(TECHNICIAN)

CM

JUN 06 2012