

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-10240-00-00
Spot: NESENWNW Sec/Twnshp/Rge: 18-27S-12W
4421 feet from S Section Line, 4155 feet from E Section Line
Lease Name: SICU Well #: 11
County: PRATT Total Vertical Depth: 4324 feet

Operator License No.: 31739
Op Name: IUKA-CARMI DEVELOPMENT LLC
Address: PO BOX 847
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4200		WITH 2 SX CMT
PROD	5.5	4324	0	WITH 200 SX CMT
SURF	8.625	439		WITH 250 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 05/24/2012 9:00 AM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: GARELD INSLEE Company: IUKA-CARMI DEVELOPMENT Phone: (620) 672-9571

Proposed Plugging Method: SET CIBP @ 4200' & PUT 2 SX CMT ON TOP OF CIBP. PERFORATE 5 1/2" @ 680'. CIRCULATE 5 1/2" CASING & 5 1/2" X 8 5/8" ANNULUS WITH CMT TO SURFACE.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/06/2012 10:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

Perfs:

SET CIBP @ 4200' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. PERFORATE 5 1/2" @ 680'. PUMP DOWN 5 1/2" WITH 300 SX CMT. INITIALLY ESTABLISHED RETURNS. PRESSURE INCREASED. LOST RETURNS THROUGHOUT REST OF JOB. DISPLACED 5 1/2" CASING PAST PERFS @ 680'. SHUT DOWN. MAXIMUM PRESSURE 1300#. DISPLACEMENT PRESSURE 400#. SHUT IN. WENT ON VACUUM. 6/6/12: BROKE CIRCULATION. PUMPED DOWN 5 1/2" CASING WITH 300 SX CMT. CMT CIRCULATED.

Remarks: **COMPLIANCE ISSUE: DENIED TA 10 YR RULE** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer
6/15/12
(TECHNICIAN)

RECEIVED

JUN 12 2012

KCC DODGE CITY

RECEIVED

JUN 14 2012

KCC WICHITA